


IMPORTANT! INTRINSICALLY SAFE WIRING INSTRUCTIONS - MODELS LC1003 AND LC1004



	SWITCH INPUTS (SEE NOTE 1)	
BOARD #1	INPUT 1	LIGHT #1
	INPUT 2	LIGHT #2
BOARD #2	INPUT 1	LIGHT #3
	INPUT 2	LIGHT #4

IMPORTANT NOTES - READ CAREFULLY BEFORE INSTALLATION

1. INPUT WIRING: USE STANDARD 2 CONDUCTOR 18 OR 22 AWG UP TO 5000 FEET.
2. DRY CONTACT SWITCH OUTPUT: WIRE TO COMMON AND EITHER NORMALLY OPEN OR NORMALLY CLOSED FOR DESIRED SWITCH CONTACT. OUTPUT RATED 3 AMPS AT 120 VAC.
3. WARNING: TO INSURE INTRINSIC SAFETY, A 12 AWG WIRE MUST BE CONNECTED TO EACH TERMINAL. EACH WIRE MUST THEN BE CONNECTED TO THE SYSTEM EARTH GROUND (GROUND BUSS BAR) IN THE SAME SERVICE PANEL AS LC POWER. A GROUNDING ROD, COLDWATER PIPE OR OTHER CONNECTION SHOULD NOT BE USED.
4. INTRINSIC SAFETY COVER/BARRIER MUST REMAIN IN PLACE.

⚠ WARNING

Refer to LC installation manual for WARNINGS and CAUTIONS before proceeding. FAILURE TO COMPLY MAY RESULT IN PERSONAL INJURY, PROPERTY LOSS AND EQUIPMENT DAMAGE.



120 FINN COURT FARMINGDALE, N.Y. 11735